April 19, 2019

CITY FORT PIERCE

SOUTH 7TH STREET ROADWAY IMPROVEMENTS

BID NO. 2019-013

ADDENDUM NO. 2

The purpose of this addendum is to respond to questions submitted by potential bidders for clarification of the proposal specifications:

1. **QUESTIONS:** The scale on the sanitary sewer seems to be incorrect.
ANSWERS: **The sanitary sewer drawing scale is noted as 1" = 30; this should be revised to reference a drawing scale of 1" = 20'.**

2. **QUESTIONS:** On sheet 5 of 7 of the Roadway plans, it calls to sleeve existing sewer into ductile iron pipe. FPUA specs says carrier pipe should be ductile iron and sleeve pipe should be steel.
ANSWERS: **The casing should be DIP and the carrier pipe shall be PVC with Fernco connections to the existing clay pipe**

3. **QUESTIONS** One of the mentioned carrier pipe inside of sleeve pipe (see note for structure S-14) is in an intersection. FPUA spec states to extend 8" beyond roadway. I am not sure how to address this
ANSWERS: **Please provide additional information as I could not find any reference to 8" beyond a roadway.**

All other conditions of this bid remain the same.

Please acknowledge receipt of this addendum and include it with your submittal.

Signature:_____
Manual

Signature:_____
Typed or Printed

Company Name:_____

Address:_____

_____

Date:_____

/lh